



CLIENTS, DESIGNERS AND PLANNING SUPERVISORS

ADVANCE NOTICE OF HSE INITIATIVE

During March 2003 HSE Inspectors will be visiting construction sites throughout East and South East England checking that risks from **mobile construction plant, vehicles and lifting operations** are being properly controlled.

These visits are part of a national rolling programme of blitzes planned by the HSE Construction Division. HM Inspectors will adopt a rigorous approach to checking on the safety of mobile construction plant, vehicles and lifting operations. Work may be prohibited and prosecution action taken where there is serious failure to control risk and / or comply with the law.

The CDM Regulations place duties on **clients, designers and planning supervisors** to eliminate and contribute to risk control on construction projects through risk assessment and the health and safety plan. I have therefore summarised below the matters that may be considered during the visits. The client is required to ensure that construction does not start unless the principal contractor has prepared a compliant health and safety plan.

Prior to the visits you may wish to review what you are doing currently in respect of these matters.

MATTERS THAT MAY BE CONSIDERED DURING THE VISITS

- **Safe Site** - availability of a traffic management plan, separation of plant and vehicles from pedestrians, the control of reversing or slewing operations, use of high-visibility clothing and the maintenance of traffic routes
- **Safe Plant and Vehicles** - the maintenance of critical controls, warning devices and visibility aids etc., authorisation to drive plant and vehicles, all round visibility by provision and use of sufficient mirrors, CCTV etc, roll-over protection and seat belts.
- **Safe Driver** - possession of training certificates that have been checked, operation of plant and driving of vehicles in a safe manner, induction carried out including information on the traffic management plan.
- **Safe Lifting Operations** - Inspectors will wish to check: whether it is a "crane hire" or "contract lift", who is appointed to plan the lift, who is supervising the lift and the presence of a lifting plan / method statement. Particular attention will be paid to lifting plan information about the lifting tackle to be used, the competency of those persons given the task of slinging loads and the specification of the mobile crane outrigger support.

If you have any queries about this initiative please contact my colleague Philip Poynter on 01582 444200

Philip White
Head of Operations
Health and Safety Executive Construction Division
London East and South East Region